


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:



Set a granite stone 16x10x4 ins 11 ins in the ground for ¼ sec cor marked ¼ on N face from which:  
 A pine 40 in diam bears N68°W 41 lks dist marked ¼S BT  
 A pine 36 in diam bears S36°E 91 lks dist marked ¼S BT  
 Corner remonumented in 1977 by Craig L. Wanless, BLM Group no. 350. His notes state: The ¼ cor of secs 5 and 32, on the S boundary of the Tp monumented with the original unmarked granite stone, 16x10x4 ins firmly set 4 ins in the ground in a collar of stones, from which the remains of the original bearing trees; A sawed pine stump, 41 ins diam, bears N68°W 41 lks dist with scribes visible. A pine snag 38 ins diam bears S36°E 91 lks dist with scribes visible. At the corner point set an iron post in a mound of stone 2 ft base to top with brass cap marked; (markings shown below) from which new bearing trees: A pine 10 ins diam bears N14°W 32 lks dist marked ¼ S32 BT. A pine 10 ins diam bears S27°W 47 lks dist marked ¼ S5 BT.  
 Deposit corner stone alongside iron post.  
 No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:


Found a standard BLM brass cap marked as shown, in a mound of stone.

Original BTs:

Found an 34 inch diameter pine snag S36°E, 91 lks dist, dead and standing with blaze evident.  
 Found a 39 inch diameter Pine stump N68°W, 41 lks dist, rotting with scribes visible.

BLM BTs:

Found a 12 inch diameter Douglas Fir S27°E, 47 lks dist, sick and dying with blaze evident.  
 Found a 14 inch diameter Douglas Fir N14°W, 32 lks dist, sick and dying with blaze evident.



NOTE:

BLM record states taking pine bearing trees.

Description of monument and accessories I established to perpetuate the

original location of this corner: From the existing found BLM brass cap monument:

New BTs:

A 10 inch diameter Ponderosa Pine bears N17°E, 43.68 feet marked ¼ S32 BT  
 A 10 inch diameter Ponderosa Pine bears S18°E, 70.84 feet marked ¼ S5 BT

Painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

Set a steel fencepost approximately 5 feet East with 54-2 and 54-9 signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 21, 1987.

Witness: Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept County of Umatilla  
 State of OR, I hereby certify that the within instrument was filed in this office  
 for record on the 21st day of August, 1987  
David L. Campbell by Kathleen K. Mabrey  
 (COUNTY OFFICIAL) (DEPUTY)

87-47-e