

A - 7
DIAGRAM

History of original corner establishment:

The original corner was established by Frank W. Campbell on June 21, 1883, under GLO contract No. 468 as follows: Set granite stone, 16" x 10" x 4", for 1/4 section corner, from which: A 40" Pine bears N68°W, 41 links (27.06 feet). A 36" Pine bears S36°E, 91 links (60.06 feet). In 1977, the BLM found the stone, 16" x 10" x 4", solidly set in a mound of stones, from which: A 41" sawn pine stump bears N68°W, 41 links. A 38" pine snag with visible scribes bears S36°E, 91 links. The BLM set a 2 1/2" iron post with a brass cap marked as shown in the diagram, from which: A 10" pine bears N14°W, 32 links (21.12 feet). A 10" pine bears S27°W, 47 links (31.02 feet). In 1987, Duane I. Griffith found the BLM brass capped iron pipe, and the following bearing trees: A 34" Pine snag with a blaze bears S36°E, 91 links. A 39" Pine stump with scribes visible bears N68°W, 41 links. A 12" sickley Douglas-fir with a blaze bears S27°E, 47 links. A 14" sickley Douglas-fir with a blaze bears N14°W, 32 links. Griffith scribed the following new bearing trees: A 10" Ponderosa Pine bears N17°E, 43.68 feet. A 10" Ponderosa Pine bears S18°E, 70.84 feet.

T6S R33E
1/4 S32
S5
T7S
1977


Description of corner evidence found:

- A 2 1/2" iron pipe with a 3 1/4" brass cap attached. The brass cap is protruding 4" above the ground and is surrounded by a mound of stones. The cap is marked with the BLM logo and as shown in the diagram above, from which:
- A badly burnt pine stump bears N63°W, 27.0 feet.
- A down and burnt pine log with charred scribes visible, root hole bears S35°E, 67.0 feet.
- A 13" Douglas-fir snag with a healed blaze bears N13°30'W, 21.1 feet.
- A 12" Douglas-fir snag with a healed blaze bears S28°W, 30.3 feet.
- A 9" Ponderosa Pine snag with charred scribes visible on double blazes bears N21°E, 43.6 feet.
- A 10" Ponderosa Pine snag with burnt out double blazes bears S15°30'E, 70.8 feet.

Description of monument and accessories I established to perpetuate the original location of this corner:

- I establish the following new references:
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S32 NE", attached at ground level, bears N25°30'E, 41.1 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S5 SE", attached at ground level, bears S43°45'E, 76.9 feet.
 - A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S5 SW", attached at ground level, bears S67°15'W, 55.5 feet.
 - A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S32 NW", attached at ground level, bears N43°W, 61.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 12, 1997. Magnetic declination: 20°E.


 DENNIS L. GAYLORD
 1636
Renews 6/30/97

B-7
 RECEIVED BY
 Umatilla County Surveyor
 Date 4-97
 Rec'd By KR
 No. 97-79-R