

USDA-FOREST SERVICE

Index

File No.

T. 7 S. R. 33 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON

Tract or

Survey No. NFJD Unit

Cor.

No. AP-338

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5507 travel southerly on 5507 approx. 6.31 miles to a small draw. Walk southwesterly down the draw approx. 600 feet to the corner.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,462,971.55'

Y: 485,632.89'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06-1992

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, 26" in the ground, marked "USDA WILDERNESS BOUNDARY NO 338 RLS 2308 1992 FOREST SERVICE".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

28" Ponderosa Pine, S. 73 1/4° E., 38.0 ft., mkd. "WB/338""BT" on single blaze.

19" Ponderosa Pine, N. 31° W., 32.0 ft., mkd. "WB/338"BT" on single blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing.

Work Done By **D. Schlaich**

Title Land Surveyor

Date 06-1992

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At

Date

REMARKS

Index File No.

T.

7 S.

R.

33 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-338