

USDA-FOREST SERVICE

Index

File No.

T. 7 S.

R. 33 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NOTH FORK JOHN DAY

N.F. UMATILLA

County GRANT

State OREGON

Tract or

Survey No. NFJD UNIT

Cor.

No. AP-3301C

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

AP-3301C



PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct of roads 1010 and 1010-180 walk northwesterly on 1010-800 approx. 0.26 miles. Then walk northeasterly 200 feet to AP-3301. Then follow the marked wilderness boundary N. 45 3/4° E., 6345 feet to the corner.

PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,471,164.83'

Y: 459,866.32'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06/26/92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, mkd. "NFJD WILDERNESS AP-3301C RLS 2308 1992".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

15" Western Larch, S. 84 1/2° E., 40.2 ft., mkd. "WB/3301C""BT".

17" Western Larch, S. 73 1/2° W., 35.9 ft., mkd. "WB/3301C""BT".

The BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich

Title Land Surveyor

Date 06/26/92

State Registration No.
or Agency

Certified Cor. Record Prepared? NO

Filed At

Date

REMARKS

Index File No.

T.

7 S.

R.

33 E.

M.

W.M.

Tract or Survey No.

NFJD UNIT

Cor.

AP-3301C