

Oregon and Washington Boundary Line.

		<p>and 9 ins. sq., when trimmed; top beveled; ground end charred. Marked on N. face "W", on S. "O", on E. "46° L 1864", on W. "10 M". Built mound, 8 ft. sq. at base & rising to post 3½ ft., composed partly of stone and covered with soil. Dug trench & pits of the usual size.</p> <p>Bearings:</p> <p>To ledge of rock, projecting from ridge top, N.82°09'W., dist. 50 chs.</p> <p>To a similar object, S.9°01'30"W., dist. 1 1/3 miles.</p> <p>Point at which horizon is intercepted by ridge, S.48°02' E., dist. 1 mile.</p>
S.13-14		<p>Gradually ascending over poor stony soil, 9.75 chs., intersected N. & S. line bet. Sees. 13-14, at back-bone of elevated, flat topped ridge, which brs. S.E. Deposited charred stake; built mound around post, properly marked. Dug trench, pits, etc., as prescribed in "Manual of Surveying Instructions."</p>
1864 May 30		<p>Descending from ridge, pass over several small foot hills, 40 chs., terminates on flat, surrounded by high ridges, which bear in all directions.</p>
1/2 M.		<p>Bearings:</p> <p>To rocks, projecting from ridge, N.75°20' E., dist. 1½ miles. Made excavation, 2½ ft. deep; deposited charred stake, 16 ins. long. Planted post 6½ ft. long & 5 ins. sq.; top beveled; ground end charred; marked on W. side "½ M". Erected a large & very durable mound with trench, pits, etc. Thence over broken country, cut up by ridges and ravines, bearing no general direction. 77 chs., cross gully with faint trail; ascend hill to end of 80 chs.</p>
11 M.		<p>Bearings:</p> <p>To edge of rocky bluff, N.27°43' W., dist. ½ mile.</p> <p>To large "Bolder" on hillside, dist. 15 chs., S.81°50' 30" E. Made excavation, 3 ft. deep; deposited charred stakes. Planted a charred willow post, 8 ft. long & 9 ins. sq., when trimmed; top beveled; marked on N. face "W", on S. "O", on E. "46° L 1864", and on W. "11 M."</p>