

Oregon and Washington Boundary Line.

1864 June 3	<p>Erected post with "prescribed" inscription. Built mound of earth, 3 ft. sq. at base and 2 ft. high, tapering to post. Dug deep trench, pits, etc., similar to the preceding Sec. mounds. Thence over undulating prairie, at end of 40 chs. marked Bdy.</p>
1/2 M.	<p>Bearings:</p> <p>To largest & W. projecting rock, S.12°28'W., dist. 60 chs. To rock on mountain side, S.35°15'E., dist., 3 miles. Conical mound, N.40°30'W., dist. 6½ miles.</p> <p>Erected post, 6 ft. long & 4 ins. sq. marked on W. side "½ M". Built mound, 6 ft. sq. & 3 ft. high; sodded; dug rectangular trench & 4 pits. This mound is situated on a slight decline to N. The Bdy. then passes along the edge of a N.W. decline in the prairie to the 80 chs. which terminate in level prairie about 60 chs. N. of ft. spurs of Mt., the main chain bearing W.N.W.</p> <p>Bearings:</p> <p>To conical mound, N.44°18'W., dist. 7 miles. To edge of rock, projecting from near ft. of ridge, S. 21°52'E., dist. 1 mile. Center of W. rock, on lower part of ridge, S.56°21'W., dist. 70 chs.</p>
15 M. S 14-15	<p>Made excavation, 3 ft. deep; deposited charred white thorn stake, 12 ins. long & 4 ins. diam. Planted post, 8 ft. long & 6 ins. sq.; trimmed; top beveled & deeply marked on N. face, "W", on S. "O", on E. "46° L 1864", on W. "15 M." Built earthen mound, 8 ft. sq. at base & 4 ft. high, tapering to post; earth well packed & sodded. Dug deep trench, pits, etc. Thence over level prairie at 9.50 chs. intersected N. & S. line bet. Secs. 14-15, T 6 N R 33 E.</p>
	<p>Bearings:</p> <p>To upper ledge of projecting rocks, S.19°09'E., dist. 1 mile. Lone rock on side of mountain, S.45°05'W., dist. 1½ mile. S. edge of small ridge, N.50°27'W., dist. 8½ miles.</p> <p>Erected properly marked Sec. post. Built mound; dug pits & trench. Thence over gradual rise in prairie, 40 chs.</p>