

Oregon and Washington Boundary Line:

terminate on slight decline to N.E. and a few chains S. of well defined depression to the N.W.

Bearings:

To highest projecting rock, from end of ridge, S.28°37' W., dist. 1½ mile.

To similar object, S.8°28' E., dist. 1 mile.

1/2 M. Planted a poplar post, 7 ft. long & 5 ins. sq. Marked on W. side, "½ M." Built mound of earth, 6 ft. sq. & 3½ ft. high, tapering to post; mound packed & sodded. Dug trench & pits of usual size & location.

1864 June 4 Leaving this post, the Bdy. passes up the bed of a slight decline, for a dist. of 20 chs. and thence over ill-defined ridges; 80 chs. terminate on slope to S.

16 M. Bearings:

To Conical mound, N.50°08'W., dist. 8 miles.

To edge of highest projecting ledge of rock on bluff ridge, S.44°23'W., dist. 1½ miles.

To center of small grove of timber on Pine Creek, S.66°53'E., dist. 5½ miles.

Planted a large cottonwood post, 9 ft. long, 8 ins. sq.; top beveled; marked on N. face "W", on S. "O", on E. "46° L 1864", on W. "16 M." Built mound, 8 ft. sq. & 4 ft. high, tapering to post. Earth packed & sodded; deposited bones; dug rectangular trench, also pits, etc.

Up slight rise and near its top, 9.50, intersection of S 13-14 N.&S. line bet. Secs. 13-14, T 6 N R 33 E.

Bearings:

To conical mound, N.50°14'W., dist. 8 miles.

To highest projecting rock, E. end of ridge, S.47°24'W., dist. 1½ miles.

To a similar object, S.39°50'W., dist. 3½ miles.

Erected poplar post, properly marked; built mound of earth; dug pits, etc., as usual. Thence over gentle swell rise. (Descend gradually; 40 chs. end on E. slope of small rise.)

Bearings:

To highest rock abutting from E. ridge, S.39°25'W., dist. 1½ miles.