

Oregon & Washington Boundary Line.

	51' W., dist. 6 miles.
14-15	Ascend over gradual rise, 6.40 chains, to intersection of N. & S. line, bet. Secs. 14- 15, T 6 N R 34 E situated about midway on slope of hill, declining to S.S. W.
1864 June 9	Deposited a yellow stone, 5 ins. diam. Planted a cottonwood post of prescribed size & marking. Built mound with pits, etc.
	Bearings: To well defined Mt. gap, S.59°20'E., dist. 35 miles. Middle point bet. two S.W. cottonwood trees, in small grove, dist. 4 miles, S.61°18'E. To log house, S.86°57'W., dist. 1 mile. Thence ascend and enter upon rolling prairie ridges. 40 chs. on top of ridge, bearing E. N. E.
1/2 M.	Bearings: To well defined Mt. gap, S.58°58'E., dist. 34½ miles. Small Mt. peak, near Columbia River, N.78°47'W., dist. 17 miles. Mt. peak with timber, N.77°26'E., dist. 28 miles. House, S.52°14'W., dist. 3½ miles. Made excavation; deposited charred stake; erected 6 ft. alder post, 4 ins. diam. Marked on W. side "½M". Built mound; dug trench, pits, etc., similar to the usual ½ mile monuments. Thence the Bdy. crosses ravine and traversing several small ill defined ridges; 77 chs. cross trail. 80 chs. situated on slope of small hill, descending S. & S.S.W.
22 M.	Bearings: To two trees on bare Mt. ridge, S.33°11'E. Point in which dist. Mt. ridge is shut out by near hill, N.81°05'W. To a similar point, S.83°43'W. Made excavation; deposited charred stakes; planted cottonwood post, 8 ft. long, & 8 ins. sq. Top beveled; sides trimmed; marked in deeply cut characters, as usual, except W. face "22 M". Earthen mound, 8 ft. sq. at base,