

## Oregon &amp; Washington Boundary Line.

4 ft. high, tapering to post, well packed & sodded. Dug deep rectangular ditch, also 4 pits at cardinal points. This mound is nearly surrounded by small hills. Bdy. passes bet. slight depression of hills, 5.70 chs. W.S.W. slope, near head of small ravine, intersected N. & S. line bet. Secs. 13-14, T 6 N R 34 E.

## Bearings:

To lone tree in dist. Mt. ridge, S.32°52'E., dist. 12 miles.

Rock at head of ravine, S.27°11'W., dist. 6 miles.

Yakima Mt. peak, N.76°24'W., dist. 50 miles.

Erected post, properly marked; built mound; dug pits, etc., as usual. Passing over gradually ascending country, without any noticeable feature to the end of 40 chs.

## Bearings:

To Mt. peak, with clump of timber, N.77°04'E., dist. 27 miles.

S.W. cottonwood on Walla Walla River, N.40°09'W., dist. 4½ miles.

Twin trees on dist. Mt. ridge, S.31°27'30"E., dist. 12 miles.

Rock abutting from side of Mt. ridge, S.51°36'W., dist. 6 miles.

1/2 M. Made excavation 2½ ft. deep. Planted alder post, 6 ft. long and 4 ins. sq.; marked on W. side "1/2 M". Built mound of earth; sodded; dug trench, pits, etc. Proceeding 42 chs. slight descent to gradual rolling prairie, with a marked decline S.W. 77 chs. cross road to old Hudson Bay Co.'s farm. 80 chs., mile ends in level prairie.

## Bearings:

To Mt. peak, with timber on top, N.77°09'E., dist. 35 miles.

Twin trees on dist. ridge, S.29°54'E., dist. 11½ miles.

Center of small grove of timber, S.6°10'W., dist. 5 miles.

To large cottonwood tree, dist. 6 miles, on Walla Walla River, N.53°07'W.