

Baseline through Ranges 28 and 29 East.  
 Surveyed by David P. Thompson under contract No. 79.  
 Dated July 26, 1858.

Chains	East on South boundary of sec. 36. * * * * *
80.00	Set post for corner to Township 1, North of Ranges 28 and 29 East and build mound of Earth &c as per instructions.
169th Mile T. 1 N., R. 29 E.	
	East on South boundary of sec. 31. Var. 19° 05' East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 31 and 32 and build a mound of Earth as per instructions. Land, very steep and stony. Soil, 3rd rate.
170 th Mile	
	East on South boundary of sec. 32. Var. 13° 30' East.
1.00	Top of hill. Descend.
40.00	Set post for $\frac{1}{4}$ sec. corner and build mound of Earth &c as per instructions.
79.00	Butter Creek course N.W., foot of hill make and offset 30 links South.
80.00	Set witness post for corner to secs. 32 and 33, 30 links South of true corner and build mound of Earth &c as per instructions. Land, 2nd rate, hilly. Soil, 2nd rate. June 6, 1859.
171st Mile	
	East on South boundary of sec. 33. Var. 20° East.
4.35	Leave Butter creek, 50 links wide, runs West. Offset 30 links North to true line.