

T. 1 N., R. 28 E.

Chains	North on East boundary of sec. 12. Var. 19° 45' East.
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for corner to secs. 6, 7, 1 and 12, built mound of Earth as per instructions. Land, gently rolling, slopes N., 2nd rate.
	North on East boundary of sec. 1. Var. 20° 45' East.
40.00	Set post for qr. sec. cor., built mound of Earth as per instructions.
74.93	To the corner established for the N.E. corner of T. 1 N., R. 28 E.
	This error of 5 chains went through the Township, and I destroyed the old corners and made new ones. 5 chains North of the place where previous set. May 25, 1860.
	Resurvey of Base Line through 29 East. Surveyed by L. F. Cartee under contract No. 88. Dated May 11, 1860.
	To correct this line, I commence at the established corner for Township 1 N., R. 29 and 30 and run. West on South boundary of sec. 36. Var. 22° East.
40.00	Set post for qr. sec. cor., built mound of Earth as per instructions.
80.00	Set post and a stone 10 ins. long by 4 ins. for corner to sections 35 and 36, built mound of Earth as per instructions. Land, gently rolling. Soil, 2nd rate.