

Base Line, Range 29 East.

Chains		
	West on South boundary of sec. 35.	
	Var. 22° 30' East.	
00.00	Descend hill, slopes S.W.	
30.00	Ascend hill, slopes S.E.	-400
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
50.00	Top of hill, a ridge N.E. and S.W.	+200
80.00	Set post for corner to sections 34, and 35 and built mound of stone as per instructions.	
	Land, broken.	
	Soil, 2nd and 3rd rate.	
<hr/>		
	West on South boundary of section 34.	
	Var. 23° East.	
.00	Ascend ridge nearly N. and S.	
8.00	Descend ridge nearly N. and S.	
40.00	Set post for qr. section cor. and built mound of Earth as per instructions.	-400
80.00	Set post for corner to sections 33 and 34 and built mound of Earth as per instructions.	
	Land, broken.	
	Soil, 2nd and 3rd rate.	
<hr/>		
	West on South boundary of sec. 33.	
	Var. 20° 15' East.	
40.00	Set post for qr. section cor. and built mound of stone as per instructions.	
79.00	Trail, course N. 60° W.	
80.00	Set post for corner to sec. 32 and 33 and built mound of stone as per instructions.	
	Land, rocky, 2nd rate.	
<hr/>		
	West on South boundary of sections 32.	
	Var. 20° East.	
1.50	Creek, 25 lks. wide, course N. 60° W.	
3.00	Ascend hill, faces N.E.	