

Subdivisions of T. 1 N., R. 29 E.

Chains 79.70	To section course. Land, rolling. Soil, 2nd rate.
40.00	North between sections 26 and 27. Set post for gr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for corner to sections 22, 23, 26 and 27 and built mound of Earth as per instructions. Land, gently rolling. Soil, 2nd rate.
40.00	East, on random line between secs. 23 and 26. Var. 19° 45' East. Set temp. gr. section post.
79.10	Intersect line, 44 links S. of post. S. 89° 41' W., on true line, between secs. 23 and 26.
39.55	Set post for gr. sec. corner and built mound of Earth as per instructions.
79.10	To section corner. Land, rolling. Soil, 2nd rate.
40.00	North between sections 22 and 23. Set post and deposited 2 stones, 4 ins square, for gr. sec. cor. and built mound of Earth as per instructions.
41.60	Trail, course E. and W.
80.00	Set post for corner to sections 22, 23, 14 and 15 and built mound of Earth as per instructions. Land, rolling, slopes North. Soil, 2nd rate.
40.00	East, on random line between secs. 14 and 23. Var. 20° 15' East. Set temp. gr. sections corner.
79.10	Intersect line, 24 lks. N. of post.