

## Subdivisions of T. 1 N., R. 29 E.

Chains	East, on random line, between secs. 2 and 11. Var. 19° 45' East.
40.00	Set temp. qr. sec. post.
79.20	Intersect at sec. corner. West on true line, between sections 2 and 11.
39.60	Set post for qr. sec. corner and built mound of Earth as per instructions.
79.20	To section corner. Land, rolling. Soil, 2nd rate.
	North, on random line, between secs. 2 and 3.
40.00	Set temp. qr. sec. post.
78.40	Intersect line, 108 lks. East of corner. S. 46' E., on true line, between sections 2 and 3.
38.40	Set post for qr. sections cor. and built mound of Earth as per instructions.
78.40	To sections corner. Land, slopes gently to the North. Soil, 2nd rate.
	North between sections 33 and 34.
0.00	Ascend hill, slopes South.
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for corner to sections 27, 28, 33 and 34, and built mound of Earth as per instructions. Land, broken. Soil, 2nd and 3rd rate.
	East, on random line, between secs. 27 and 34. Var. 19° East.
40.00	Set temp. qr. sec. corner.
80.00	Intersect line, 6 lks. S. of post. S. 89° 57' W., on true line, between secs. 27 and 34.
40.00	Set post for qr. sec. cor. and built mound of Earth