

Subdivisions of T. 1 N., R. 29 E.

Chains	as per instructions.
80.00	To section corner. Land, gently descending to the North. Soil, 2nd rate.
	North between sections. 27 and 28.
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for corner to sections 21, 22, 27 and 28, and built mound of stone as per instructions. Land, sloping to the North. Soil, 2nd rate.
	East, on random line, between secs. 22 and 27. Var. 22° East.
40.00	Set temp. qr. sec. post.
80.70	Intersect line, 10 lks. S. of post. S. 89° 56' W., on true line, between secs. 22 and 27.
40.35	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.70	To section corner. Land, rolling, slopes North. Soil, 2nd rate.
	North between sections 21 and 22.
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
46.50	Trail, E. and W.
80.00	Set post for cor. to secs. 15, 16, 21 and 22, and built mound of Earth as per instructions. Land, rolling, slopes North. Soil, 2nd rate.
	East, on random line, between secs. 15 and 22. Var. 20° 30' East.
40.00	Set temp. qr. sec. post.