

## Subdivisions of T. 1 N., R. 29 E.

Chains	
80.82	Intersect line, 22 lks. S. of Post. S. $89^{\circ} 51'$ W., on true line, between secs. 15 and 22.
40.41	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.82	To sections corner. Land, rolling, slopes North. Soil, 2nd rate.
	North between sections 15 and 16.
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for corner to sections 9, 10, 15 and 16, and built mound of Earth as per instructions. Land, gently rolling. Soil, 2nd rate, slopes North.
	East, on random line, between secs. 10 and 15. Var. $19^{\circ} 30'$ East.
40.00	Set temp. qr. sec. cor.
80.70	Intersect line, 38 lks. South of sec. cor. S. $89^{\circ} 44'$ W., on true line, between secs. 10 and 15.
40.35	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.70	To section corner. Land, rolling. Soil, good, 2nd rate.  May 17, 1860.
	North between sections 9 and 10.
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for cor. to secs. 9, 10, 3 and 4, and built mound of Earth as per instructions. Land, gently rolling. Soil, 2nd rate.