

Subdivisions of T. 1 N., R. 29 E.

Chains		
	East, on random line between secs. 3 and 10. Var. 21° 30' East.	
40.00	Set temp. qr. sec. post.	
80.80	Intersect line, 24 lks. S. of Post. S. 89° 45' W., on true line between secs. 3 and 10.	
40.40	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
80.80	To section corner. Land, rolling, slopes North. Soil, 2nd rate.	
	North on random line, between secs. 3 and 4.	
40.00	Set temp. qr. sec. post.	
77.81	Intersect line, 54 lks. East of post. S. 23' E., on true line, between secs. 3 and 4.	
37.81	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
77.81	To sections corner. Land, gently rolling, sloping North. Soil, 2nd rate.	
	North between sections 32 and 33.	
0.00	Ascend hill, course N. 80° W.	
2.75	Trail E. and W.	
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.	+400
80.00	Set post for corner to sections 28, 29, 32 and 33 in mound of Earth as per instructions. Land, broken. Soil, 2nd and 3rd rate.	-200
	East, on random line, between secs. 28 and 33. Var. 20° East.	
40.00	Set temp. qr. sec. post.	
80.14	Intersect line, 14 lks. N. of cor. N. 89° 54' W., on true line, between secs. 28 and 33.	