

## Subdivisions of T. 1 N., R. 29 East.

Chains 40.07	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
80.14	To section corner. Land, broken and stony. Soil, 2nd and 3rd rate.	
North between sections 28 and 29.		
0.00	Ascend hill, slopes S.W.	
40.00	Set post for qr. sec. cor. and built mound of stone as per instructions.	+300
55.00	Top of hill, E. and W.	+200
80.00	Set post for corner to secs. 20, 21, 28 and 29, and built mound of Earth as per instructions. Land, rough. Soil, 2nd and 3rd rate.	
East, on random line, between secs. 21 and 28. Var. 23° East.		
40.00	Set temp. qr. sec. cor.	
79.74	Intersect line, 45 lks. S. of post. S. 89° 41' W., on true line, between secs. 21 and 28.	
39.87	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
79.74	To section corner.	
North between sections 20 and 21.		
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
60.00	Trail, E. and W.	
80.00	Set post for corner to secs. 16, 17, 20 and 21, and built mound of stone as per instructions. Land, broken, slopes N.W. Soil, 2nd rate and stony.	
East, on random line, between sections 16 and 21.		
40.00	Set. temp. qr. sec. cor.	