

Subdivisions of T. 1 N., R. 29 E.

Chains	
80.10	Intersected line, 62 lks. S. of corner. S. 89° 33' W., on true line, between secs. 16 and 21.
40.05	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.10	To section corner. Land, rolling, slopes S.W. Soil, 2nd rate.
North between sections 16 and 17. Var. 22° 15' E.	
40.00	Set post for qr. sec. corner and built mound of Earth as per instructions.
80.00	Set post for corner to secs. 8, 9, 16 and 17, and built mound of Earth as per instructions. Land, gently descending to the North. Soil, good, 2nd rate. May 18, 1860
East, on random line, between sec. 9 and 16. Var. 15° East.	
40.00	Set temp. qr. sec. cor.
79.54	Intersected line, 90 lks. S. of cor. S. 89° 21' W., on true line, between secs. 9 and 16.
39.77	Set qr. sec. post and built mound of Earth as per instructions.
79.54	To section corner. Land, rough and stony. Soil, 3rd rate.
North between sections 8 and 9.	
40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.00	Set post for cor. to secs. 4, 5, 8 and 9, and built mound of Earth as per instructions. Land, gently rolling. Soil, 2nd rate.