

Subdivisions of T. 1 N., R. 29 E.

Chains	
	East, on random line, between secs. 4 and 9. Var. 20° 15' East.
40.00	Set temp. gr. sec. cor.
80.00	Intersected at corner.
	West, on true line, between secs. 4 and 9.
40.00	Set post for gr. sec. cor. and built mound of Earth as per instructions.
80.00	To section corner. Land, broken. Soil, 2nd and 3rd rate.
	North, on random line, between secs. 4 and 5.
40.00	Set temp. gr. sec. corner.
77.40	Intersect town line, 93 lks. East of post. S. 40° E., on true line, between secs. 4 and 5.
37.40	Set gr. sec. cor. and built mound of Earth as per instructions.
77.40	Intersect line at corner. Land, gently descending to the North. Soil, good, 2nd rate.
	North between sections 31 and 32.
40.00	Set gr. sec. cor. and built mound of stone as per instructions and descend hill, E and W.
80.00	Set post for cor. to secs. 29, 30, 31 and 32 and built mound of Earth as per instructions. Land, rough. Soil, 2nd rate.
	East, on random line, between secs. 29 and 32. Var. 19° 30' East.
40.00	Set temp. gr. sec. cor.
80.94	Intersect at sec. cor.
	West, on true line, between secs. 29 and 32.
40.47	Set post for gr. sec. cor. and built mound of Earth as per instructions.