

Subdivisions of T. 1 N., R. 29 E.

Chains	
54.00	Trail, nearly E. and W.
59.94	Creek, 25 lks. wide, course N. 80° W.
80.94	To section corner. Land, rolling, slopes S.W. Soil, 1st and 2nd rate.
West, on random line, between secs. 30 and 31.	
40.00	Set temp. qr. sec. cor.
87.14	Intersected line, 8 lks. N. of sec. cor. N. 89° 57' E., on true line, between secs. 30 and 31.
47.14	Set post for qr. sec. cor., built mound of stone as per instructions.
87.14	To section corner. Land, broken, slopes N. Soil, 2nd rate.
North between sections 29 and 30.	
17.50	Creek, 25 lks. wide, course N. 60° W.
22.50	True, course E. and W.; ascend.
40.00	Set post for qr. sec. cor. and built mound of stone (on hill side) as per instructions.
60.00	Top of hill, E. and W.
80.00	Set post for cor. to sec. 19, 20, 29 and 30, and built mound as per instructions. Land, rough. Soil, 1st and 2nd rate.
East, on random line, between secs. 20 and 29. Var. 20° East.	
40.00	Set temp. qr. sec. cor.
80.50	Intersect line, 12 lks. N. of sec. cor. N. 89° 55' W., on true line, between secs. 20 and 29.
40.25	Set post for qr. sec. cor. and built mound of Earth as per instructions.
80.50	To section corner. Land, rolling, slopes to the N. W.

+200

+300