

## Subdivisions of T. 1 N., R. 30 E.

Chains		
40.00	Set temporary quarter sec. post.	
80.08	Intersect N. and S. line 8 lks. South of corner to secs. 25, 26, 35 and 36. S. 89° 57' W., on true line, between secs. 26 and 35.	
40.04	Set post for quarter sec. corner, drove charred stake and raised mound of Earth with trench and pits as per instructions.	
80.08	The corner to secs. 26, 27, 34 and 35. Land, gently rolling prairie. Soil, good, 2nd rate.	
	North between secs. 26 and 27.	
40.00	Set quarter sec. post, drove charred stake and raised mound of Earth with trench and pits as per instructions.	
80.00	Set post for corner to secs. 22, 23, 26 and 27. Drove charred stake and raised mound of Earth with trench and pits as per instructions. Land and soil same as last mile.	
	East on random line between secs. 23 and 26. Var. 21° 15' E.	
40.00	Set temporary quarter sec. post.	+50
80.66	Intersect corner to secs. 23, 24, 25 and 26 at post. West on true line between secs. 23 and 26.	
40.33	Set post for qr. sec. cor. drove charred stake and raised mound as per instructions.	-50
46.16	To big hollow, course North.	
50.66	Cross same and ascend.	
80.66	The corner to secs. 22, 23, 26 and 27. Land, considerably rolling. Soil, good, 2nd and 3rd rate.	+150
	North between secs. 22 and 23.	
15.00	Commence steep descent.	
40.00	Set quarter sec. post on side hill. Drove charred stake and raised mound as per instructions.	-100