

## Subdivisions of T. 1 N., R. 30 E.

Chains	Soil, 2nd rate.	
	North between secs. 8 and 9.	
17.00	Cross big hollow and ascend.	
25.00	To top of ascent.	+50
40.00	Set a post for quarter sec. corner and drove charred stake and raised mound of earth as per instructions and descend.	
45.00	To foot of descent and ascend.	-25
65.00	To top of ascent.	+30
80.00	Set a post for corner to secs. 4, 5, 8 and 9. Drove charred stake and raised mound with trench and pits as per instructions.	
	Land, rolling prairie.	
	Soil, 2nd rate.	
	East on random line between secs. 4 and 9.	
	Var. 20° E.	
40.00	Set temporary quarter sec. post.	
79.88	Intersect N. and S. line corner to secs. 3, 4, 9 and 10.	
	West on true line between secs. 4 and 9.	
39.94	Set a post for quarter section corner, drove charred stake and raised mound of earth as per instructions.	
79.88	The post corner to secs. 4, 5, 8 and 9.	
	Land, rolling prairie.	
	Soil, 2nd rate.	
	November 2, 1860	
	North on random line between secs. 4 and 5.	
40.00	Set a post for quarter sec. corner temporarily.	
81.20	Intersect North boundary of Township, 50 lks. West of post, corner to secs. 4 and 5.	
	S. °21' W., on a true line between secs. 4 and 5.	
41.20	Set a post for quarter sec. corner and raised mound of earth with trench &c as per instructions.	
81.20	The corner to secs. 4, 5, 8 and 9.	