

Subdivisions of T. 1 N., R. 30 E.

Chains 47.67	Set a post for quarter section corner in stone mound as per instructions.	+50
64.67	To top of ascent.	+100
72.67	Commence descent.	
86.67	To foot of descent & Indian Trail N.E. and S.W.	-50
87.67	The corner to secs. 29, 30, 31 and 32. Land and Soil same as last mile	
	North between secs. 29 and 30. Commence ascent from post.	
6.00	Indian Trail, N.W. and S.E.	
10.50	Large Trail bears nearly N.E. and S.W.	
24.00	To top of ascent and descend.	+25
34.00	Same Trail bears N.W. and S.E.	
40.00	Set a post for quarter section corner, drove charred stake and raised mound as per instructions.	-30
80.00	Set a post for corner to secs. 19, 20, 29 and 30. Drove charred stake and raised mound as per instructions. Land, gently rolling. Soil, good, 2nd rate.	-25
	East on a random line between secs. 20 and 29. Var. $19\frac{3}{4}^{\circ}$ E.	
40.00	Set temporary quarter sec. post.	
80.18	Intersect N. and S. line, 25 lks. South of corner to secs. 20, 21, 28 and 29. S. $89^{\circ} 49'$ W. on true line between secs. 20 and 29.	
30.18	To top of ascent.	+30
35.18	Commence to descend.	
40.09	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound of earth &c as per instructions.	
62.43	To foot of descent and hollow.	-60
63.18	To Trail, course N. and S.	
80.18	The corner to secs. 19, 20, 29 and 30. Land, rolling prairie. Soil, good, 2nd rate.	