

Subdivisions of T. 1 N., R. 30 E

Chains	West on a random line between secs. 19 and 30. Var. 19° 45' E.	
40.00	Set a temporary quarter sec. post.	
87.00	Intersect West boundary of Township, 10 lks. South of post, corner to secs. 19 and 30. S. 89° 56' E. on a true line between secs. 19 and 30.	
47.00	Set a post for quarter sec. corner, drove charred stake and raised mound of earth as per instructions.	
59.00	To Trail above noted N. and S.	
87.00	The corner to secs. 19, 20, 29, and 30 Land, gently rolling prairie. Soil, good, 2nd rate.	
	North between secs. 19 and 20. Commence descending at post.	
40.00	Set a post for quarter sec. corner, drove charred stake and raised mound of earth &c as per instructions.	-100
50.00	Cross hollow and ascend.	-50
70.00	To top of ascent and descend to post.	+50
80.00	Set a post on a ridge, 150 lks. from a ravine. Drove charred stake and raised mound of earth as per instructions. Land, rolling prairie. Soil, good, 2nd rate.	
	East on a random line between secs. 17 and 20. Var. 19° 55' E.	
40.00	Set temp. quarter sec. post on side hill.	+150
80.32	Intersect N. and S. line, 24 lks. North of cor. to 16, 17, 21 and 20. N. 89° 50' W. on true line between secs. 17 and 20.	
45.32	To top of ascent and descend.	+25
40.16	Set a post for quarter sec. corner in stone mound as per instructions.	-150
67.82	To foot of descent and ascend gently.	