

Subdivisions of T. 1 N., R. 30 E.

Chains		
	secs. 8, 9, 16 and 17.	
	November 4, 1860.	
	S. 89° 55' W. on a true line between secs. 8 and 17.	
8.06	To top of a ridge descending to big hollow.	+50
22.06	To rocks cropping out.	-25
24.06	To foot of descent.	-50
28.06	To Trail, course N. and S.	
31.06	Cross bottom and commence ascent of bluff.	
40.03	Set a post for quarter sec. corner, drove a charred stake and raised mound of earth as per instructions.	+40
46.06	To rocks cropping out.	+60
72.06	To top of bluff.	
80.06	The post corner to secs. 7, 8, 17 and 18.	
	Land, much broken with several ridges and hollows running into big hollow before noted.	
	Soil, 2nd and 3rd rate.	
	West on a random line between secs. 7 and 18.	
	Var. 21° E.	
40.00	Set temporary quarter sec. post.	
86.42	Intersect West boundary of Township, 38 lks. South of post, corner to secs. 7 and 18.	
	S. 89° 44' E., on a true line, between secs. 7 and 18	
1.42	To large Indian trail, course N. and S.	
35.92	Commence to ascend.	
46.42	Set a post for quarter section corner, drove charred stake and raised mound of earth as per instructions.	
76.42	To top of hill and commence descent.	+50
79.42	To hollow and ascend.	-25
86.42	The post corner to secs. 7, 8, 17 and 18.	
	Land, rolling prairie.	
	Soil, good, 2nd rate.	
	North between secs. 7 and 8.	
	Descend gradually from post.	
27.50	To foot of descent and ascend.	-100