

East Boundary of T. 1 N., R. 31 E.

Chains	<p>North on East boundary of sec. 1.</p> <p style="text-align: right;">Var. 19° 45' E.</p> <p>40.00 Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>80.00 A point for corner to Townships 1 and 2 North, Ranges 31 and 32 East. Set post and drove charred stake, raised mound with trench as per instructions.</p> <p>Land, for the last 6 miles has been rolling grass hills.</p> <p>Soil, light 2nd rate.</p> <p style="text-align: right;">Oct. 17, 1860.</p>
	<p>Subdivisions of T. 1 N., R. 31 E. Surveyed by Josiah A. Burnett under contract No. 92. Dated September 12, 1860.</p>
	<p>Subdivisions commenced October 17, 1860.</p> <p>North between secs. 35 and 36.</p> <p>40.00 Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>50.00 To a dry Ravine, course N.E.</p> <p>80.00 Set post for corner to secs. 25, 26, 35 and 36., drove charred stake and raised mound with trench as per instructions.</p> <p>Land, rolling grass hills.</p> <p>Soil, 2nd rate.</p>
	<p>East on random line between secs. 25 and 36.</p> <p style="text-align: right;">Var. 20° 00' E.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>79.68 Intersected East boundary of Township, 63 links South of corner to secs. 25 and 36, 30 and 31, from which corner I run.</p> <p>S. 89° 33' W., on true line between secs. 25 and 36.</p> <p>39.84 Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound as per instructions.</p> <p>79.68 The corner to secs. 25, 26, 35 and 36.</p> <p>Land, level.</p> <p>Soil, 2nd rate.</p>