

Subdivisions of T. 1 N., R. 31 E.

Chains	
40.00	Set a post for $\frac{1}{4}$ sec. cor. and raised stone mound as per instructions.
50.00	Summit of hill, bearing N.W. and S.E.
80.00	Set a post for corner to secs. 16, 17, 20 and 21, drove charred stake and raised mound with trench as per instructions.
	Land, 3rd and 4th rate soil.
	East on random line between secs. 16 and 21. Var. $19^{\circ} 30' E.$
40.00	Set a temporary $\frac{1}{4}$ sec. cor.
80.31	Intersected N. and S. line, 17 lks. North of the corner to secs. 15, 16, 21 and 22, from which corner I run. N. $89^{\circ} 53' W.$ on true line between secs. 16 and 21.
40.15	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.31	The corner to secs. 16, 17, 20 and 21. Land, West half stony, East half 2nd rate soil.
	North between secs. 16 and 17.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
50.00	To a dry Ravine, course N.E.
80.00	Set post for corner to secs. 8, 9, 16 and 17, drove charred stake and raised mound as per instructions. Land, rolling grass hills. Soil, 2nd rate.
	East on random line between secs. 9 and 16. Var. $20^{\circ} 05' E.$
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.16	Intersected N. and S. line, 10 lks. South of the corner to secs. 9, 10, 15 and 16, from which corner I run. S. $89^{\circ} 56' W.$ on true line between secs. 9 and 16.
40.08	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.