

Subdivisions of T. 1 N., R. 31 E.

Chains	
52.00	To a dry ravine, course N.E.
80.16	The corner to secs. 8, 9, 16 and 17. Land, rolling grass hills. Soil, 2nd rate.
	North between secs. 8 and 9.
20.00	To a dry ravine, course East.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set a post for corner to secs. 4, 5, 8 and 9, drove charred stake and raised mound with trench as per instructions. Land, broken and stony.
	East on random line between secs. 4 and 9. Var. 20° 15' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.02	Intersect N. and S. line, 30 lks. South of the corner to secs. 3, 4, 9 and 10, from which corner I run. S. 89° 47' W. on true line between secs. 4 and 9.
40.01	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.02	The corner to secs. 4, 5, 8 and 9. Land, gently rolling table land. Soil, 2nd rate.
	North on random line between secs. 4 and 5.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
82.82	Intersect North boundary of the Township, 18 lks. East of the corner to secs. 4 and 5, from which corner I run. S. 0° 08' E. on true line between secs. 4 and 5.
42.82	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and made mound and trench as per instructions.
82.82	The corner to secs. 4, 5, 8 and 9. Land, broken.