

T. 1 N., R. 32 E.

Chains 80.00	<p>Set post for corner to secs. 34 and 35 and build a mound of earth as per instructions.</p> <p>Land, 1st rate, level, covered with grass.</p> <p style="text-align: right;">June 8th, 1859.</p>
	191st Mile
	<p>East on South boundary of sec. 35.</p> <p style="text-align: right;">Var. 19° 50' East.</p>
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of earth as per instructions.
70.25	Creek 50. lks. wide, runs N.E.
80.00	<p>Set post for corner to secs. 35 and 36 from which</p> <p style="padding-left: 40px;">A cotton wood, 10 ins. diam., bears N. 60°W.26lks. dist.</p> <p style="padding-left: 40px;">" " " 10 " " " N. 74°E.64 " "</p> <p>Land, level.</p> <p>Soil, 1st rate, creek bottom.</p>
	192nd Mile
	<p>East on South boundary of sec. 36.</p> <p style="text-align: right;">Var. 21° 25' East.</p>
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of earth as per instructions.
80.00	<p>Set post for corner to Township 1 North of Ranges 32 and 33 East and build mound of earth as per instructions.</p> <p>Land, 1st rate, level grass land.</p> <p>Termmus of the Base Line about 3 mile East to the ascent of the Blue Mountains.</p>
	General Description
	<p>For about 15 miles the Blue Mountains have been about ten miles South of the Base Line. Their sides are covered with pine and fir timber. Numerous small streams flow from their base and empty into McKays Creek, Willow and Butter Creeks.</p> <p>The land is very rich and level or gently rolling to the foot of the mountain and covered with a thick growth</p>