

T. 1 S., R. 32 E.

Chains	East on North boundary of sec. 1. Var. 21° East.
22.00	Standard sec. corner.
40.00	Set post for $\frac{3}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.
80.00	The corner to Townships 1 South, Ranges 32 and 33 East. Land, gently rolling. Soil, 2nd rate. October 13th, 1864.
Exterior Boundaries of T. 1 N., R. 32 E. Surveyed by David P. Thompson under contract No. 106. Dated August 16, 1864.	
	I commence at the established corner on base line, corner to Townships 1 North of Ranges No. 32 and 33 and run North on East boundary of sec. 36. Var. 21° East.
40.00	Set stone, 17 x 10 x 8 ins., for $\frac{1}{4}$ sec. corner.
80.00	Set post for corner to secs. 30, 31, 25 and 36, in mound of earth with charred stake, pits, trench &c as per instructions. Land, level. Soil, 1st rate prairie.
	North on East boundary of sec. 25. Var. 20° East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.
80.00	Set post for corner to secs. 24, 25, 19 and 30 in mound of earth with charred stake, pits, trench &c as per instructions. Land, level. Soil, 1st rate. Very fine grass.