

## Exterior Boundaries of T. 1 N., R. 32 E.

Chains	
	<p>32 and 33 East in mound of earth with charred stake, pits, trench &amp;c as per instructions.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Level prairie.</p>
<p>40.00</p> <p>80.00</p>	<p>From the corner to Townships 1 and 2 North, Ranges 32 and 33 East I run a random line West between said Townships setting half mile and mile posts temporarily at 40.00 and 80.00 chains.</p> <p>I find the line to be 6 miles, 8 chains and 90 lks. and the falling to be 76 lks. South of Township corner which is out of the limits allowed by the instructions and believing the error to be in the chaining of the base line because error had been found in the chaining of it at other places. I commenced at the South East corner of the Township on the base line and chain West on South boundary of sec. 36.</p> <p style="text-align: center;">Var. 21° East.</p> <p>Descend hill.</p> <p>Set <math>\frac{1}{4}</math> sec. corner in mound of earth with charred stake, pits, trench &amp;c as per instructions.</p> <p>Set stone, 38 x 8 x 8 ins., for corner to secs. 35 and 36.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p> <p style="text-align: right;">September 8th, 1864.</p>
<p>.50</p> <p>1.40</p> <p>11.25</p> <p>40.00</p> <p>42.10</p>	<p>West on South boundary of sec. 35.</p> <p style="text-align: center;">Var. 21° East.</p> <p>Dry bed of creek, course N.E.</p> <p>Corner to secs. 35 and 36 which I obliterate.</p> <p>Brook, 5 lks. wide, runs N.E.</p> <p>Set post for <math>\frac{1}{4}</math> sec. corner in mound of earth with charred stake, pits, trench &amp;c as per instructions.</p> <p>Old established <math>\frac{1}{4}</math> sec. corner on base line which I</p>