

Subdivisions of T. 1 N., R. 32 E.

Chains		
40.00	Set stone, 14 x 12 x 6, for $\frac{1}{4}$ sec. cor. Descend hill.	-300
60.00	Foot of hill.	
77.50	Enter brush, bears N.W. and S.E.	
78.50	Touch Birch Creek.	
80.00	The corner to secs. 3, 4, 9 and 10. Land, hilly. Soil, 1st rate.	
	North between secs. 32 and 33.	
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	
80.00	Set stone, 18 x 15 x 5, for corner to secs. 28, 29, 32 and 33. Land, level. Soil, 1st rate.	
	East on a random line between secs. 28 and 33.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
80.00	Intersect N. and S. line at corner to secs. 27, 28, 33 and 34 from which corner I run. West on a true line between secs. 28 and 33.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
80.00	The corner to secs. 28, 29, 32 and 33. Land, gently rolling. Soil, 2nd rate.	
	North between secs. 28 and 29. Var. $19\frac{1}{2}^{\circ}$ E.	
40.00	Set stone, 16 x 10 x 10, for $\frac{1}{4}$ sec. corner.	
80.00	Set post for corner to secs. 20, 21, 28 and 29 in mound of earth with charred stake, pits &c as per instructions. Land, rolling. Soil, 2nd rate.	