

## Subdivisions of T. 1 N., R. 32 E.

Chains	S. 89° 24' E. on a true line between secs. 30 and 31.
48.26	Set stone, 18 x 12 x 10, for $\frac{1}{4}$ sec. cor.
88.26	The corner to secs. 29, 30, 31 and 32. Land, gently rolling. Soil, good, 2nd rate.
	North between secs. 29 and 30. Var. 19° 30' E.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set stone, 18 x 8 x 8, for corner to secs. 19, 20, 29 and 30. Land, rolling. Soil, good, 2nd rate. October 23rd, 1864.
	East on a random line between secs. 20 and 29.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
79.90	Intersect N. and S. line at corner to secs. 20, 21, 28 and 29 from which corner I run.
	West on a true line between secs. 20 and 29.
39.95	Set stone, 16 x 8 x 6, for $\frac{1}{4}$ sec. cor.
79.90	The corner to secs. 19, 20, 29 and 30. Land, rolling. Soil, 2nd rate. Fine grass.
	West on a random line between secs. 19 and 30.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
88.30	Intersect West boundary, 50 lks. South of corner to secs. 19 and 30 from which I run. S. 89° 39' E. on a true line between secs. 19 and 30.
48.30	Set stone, 24 x 14 x 12, for $\frac{1}{4}$ sec. corner.
88.30	The corner to secs. 19, 20, 29 and 30. Land, rolling. Soil, 2nd rate.