

T. 1 N., R. 32 E.

Chains	<p>North on East boundary of sec. 13.</p> <p style="text-align: center;">Var. 19° 45' E.</p> <p>40.00 Set post and made earth mound for <math>\frac{1}{4}</math> sec. cor.</p> <p>80.00 Set post and made mound of earth for cor. to secs. 12, 13, 7 and 18.</p> <p>Land, nearly level.</p> <p>Soil, good.</p> <p>Grass, good.</p>
	<p>North on East boundary of sec. 12.</p> <p style="text-align: center;">Var. 21° E.</p> <p>40.00 Set post and made earth mound for <math>\frac{1}{4}</math> sec. cor.</p> <p>80.00 Set post and made earth mound for cor. to secs. 1, 12, 6 and 7.</p> <p>Land, level.</p> <p>Soil, good.</p> <p>Grass, good.</p>
	<p>North on East boundary of sec. 1.</p> <p style="text-align: center;">Var. 20° 45' E.</p> <p>5.00 Wagon Road, course N.E.</p> <p>40.00 Set stone, 17 x 14 x 8, for <math>\frac{3}{4}</math> sec. cor.</p> <p>80.00 To cor. to Tps. 1 and 2 N., R. 32 and 33 East of the Willamette Mer.</p> <p>Land, level.</p> <p>Soil, good.</p> <p>Grass, good.</p>
	<p>West on North boundary of sec. 1.</p> <p style="text-align: center;">Var. 19° 45' E.</p> <p>40.00 Set post and made earth mound for <math>\frac{1}{4}</math> sec. cor.</p> <p>80.00 Set post and made earth mound for cor. to secs. 1, 2, 35 and 36.</p> <p>Land, level.</p> <p>Soil, good.</p>