

T. 1 N., R. 32 E.

| Chains | <p style="text-align: center;">Var. 20° E.</p> |
|--------|---|
| | <p>Descending gradually.</p> |
| 39.50 | <p>To old $\frac{1}{4}$ sec. cor., found pits and earth mound. Set a basalt stone, 10 x 8 x 6 ins., 7 ins. in old md. marked $\frac{1}{4}$ on W. face. Dug pits, 18 x 18 x 12 ins., N. and S. of cor., $5\frac{1}{2}$ ft. dist. and raised earth mound. $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base along side.</p> |
| 43.00 | <p>Hollow course W.</p> |
| 69.95 | <p>Trail course N.E. and S.W.</p> |
| 79.00 | <p>Found old cor. to secs. 25, 30, 31 and 36, found pits and md. Set a basalt stone, 16 x 12 x 8 ins., 11 ins. in old md. mkd. 1 notch on S. and 5 on N. edges. Dug pits, 18 x 18 x 12 ins., in cor. of each sec. $5\frac{1}{2}$ ft. dist. Raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base along side.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p> <p>No timber. Grass short.</p> |
| | <p>North on E. boundary sec. 25.</p> |
| | <p style="text-align: center;">Var. 20° 30' E.</p> |
| 8.65 | <p>Spring branch, 2 lks. wide, c. W.</p> |
| 39.85 | <p>Found pits and mound of old $\frac{1}{4}$ sec. cor. Set a basalt stone, 12 x 10 x 10 ins., 8 ins. in the ground in old md mkd. $\frac{1}{4}$ on W. face for $\frac{1}{4}$ sec. cor. Dug pits, 18 x 18 x 12 ins., N. and S. of cor., $5\frac{1}{2}$ ft. dist., raised earth md. $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base along side.</p> |
| 79.70 | <p>To old cor. to secs. 19, 24, 25 and 30. Found pits and md. of earth. Set a basalt stone, 14 x 10 x 8 ins., 10 ins. in the ground for cor. to secs. 19, 24, 25 and 30, mkd. 2 notches on S. and 4 on N. edges. Dug pits, 18 x 18 x 12 ins., in cor. of each sec., $5\frac{1}{2}$ ft. dist. and raised earth mound 2 ft. high, $4\frac{1}{2}$ ft. base along side.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. No timber.</p> <p>Bunch Grass and rabbit sage.</p> |