

## Subdivisions of T. 1 N., R. 32 E.

Chains	high, $4\frac{1}{2}$ ft. base over it.
15.00	McKay creek, 75 lks. wide, course N.
20.00	Enter field.
25.00	Leave field.
40.00	To cor. to secs. 25, 26, 35 and 36. Land, rolling. Soil, good. Cotton-wood timber and underbrush. Sage brush and poor grass.
	North on true line between secs. 25 and 26. Var. $21^{\circ}$ East.
39.75	To old $\frac{1}{4}$ sec. cor., found mound and pits. Set stone, 8 x 10 x 16 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Redug pits, 18 x 18 x 12 ins., N. and S., $5\frac{1}{2}$ ft. dist. from stone and raised a mound of earth, 18 ins. high, $3\frac{1}{2}$ ft. base alongside.
57.00	Dry gulch, course N.W.
62.50	Creek, bottom.
79.50	Found old cor. stone to secs. 23, 24, 25 and 26, 8 x 10 x 18 ins., marked with 1 notch on E. and 2 on S. edges. I raised a mound of stone, 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, gently rolling and level. Poor bunch grass and scattering sage. No timber.
	East on random between secs. 24 and 25. Var. $21^{\circ}$ East.
40.00	Set temp. $\frac{1}{4}$ sec. cor.
79.60	Intersect Township line, 50 lks. South of cor. to secs. 24 and 25. Thence S. $89^{\circ} 39'$ W. on true line. Var. $20^{\circ}$ East.
38.80	Old $\frac{1}{4}$ cor. found pits and mound. Set stone, 8 x 12 x 14 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Redug pits, 18 x 18 x 12 ins., E. and W.

-50