

Subdivisions of T. 1 N., R. 32 E.

Chains	of earth over it.
37.00	Wire fence and leave field.
38.00	Wagon Road, bears N. and S.
40.00	Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S. on N. face. Dug pits, 18 x 18 x 12 ins., E. and W. from post, $5\frac{1}{2}$ ft. dist. I raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
62.00	Canyon, course S.W.
75.00	McKay Creek bottom.
79.00	Branch of McKay Creek, 25 lks. wide.
80.00	To cor. to secs. 2, 3, 10 and 11. Land, rolling. Soil, 1st rate. Scattering cottonwood along McKay. Poor bunch grass.

-150

July 27, 1887.

General Description.

This Township is rolling and bottom land. The bottom is gravelly and very poor with some cottonwood, thorn and willow. Rolling land good.

Topography, T. 1 N., R. 32 E.
Surveyed by Currin and Noland under special contract.
Dated May 4, 1887.

Line between secs. 10 and 11.

From cor. secs. 10, 11, 14, and 15, a basalt stone, 12 x 8 x 6 ins. firmly set in the ground with a pit in each sec. $5\frac{1}{2}$ ft. dist., stone marked with 2 notches on E. and 4 on S. edges. Pits and md. in good condition.

North between secs. 10 and 11.

Var. $20^{\circ} 30'$ E.

40.00 $\frac{1}{4}$ sec. cor.

60.00 Pendleton and Pilot Rock Road, course N.W. and S.E.