

Subdivisions of T. 1 N., R. 33 E.

Chains		
	North between secs. 33 and 34. Ascend hill.	
25.00	Top of hill, bears NW. and SE.; descend.	-400
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	
74.00	Foot of hill.	-700
80.00	Set stone, 22x14x10, for corner to secs. 33, 34, 27 and 28. Land, hilly. Soil, 2nd rate. Grass, good.	
	East on a random line between secs. 27 and 34.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
79.87	Intersect N. and S. line, 46 lks. North of corner to secs. 26, 27, 34 and 35, from which I run N.89°40'W. on a true line between secs. 27 and 34.	
	Descend hill, mountain.	
39.93	Set stone, 18x15x6, for $\frac{1}{4}$ sec. cor.	
68.00	Foot of hill.	-700
79.87	The corner to secs. 33, 34, 27 and 28. Land, hilly sloping west. Soil, 2nd rate.	
	North between secs. 27 and 28. Var. 21°E.	
	Ascend hill.	
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.	
80.00	Set post for corner to secs. 21, 22, 27 and 28 in mound of earth with charred stake, pits &c as per instructions, on top of hill, bears E. and W.	+500
	Land, hilly. Soil, 2nd rate.	