

Subdivisions of T. 1 N., R. 33 E.

Chains		
	East on random between secs. 1 and 12. Var. 20° East.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.12	Intersected N. and S. line, 14 lks. S. of cor. S. 89° 54' W. on true line.	
40.06	Set stone, 15x13x10, for $\frac{1}{4}$ S. cor.	
80.12	To corner.	
	West on random between secs. 2 and 11.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.16	Intersected N. and S. line, 12 lks. S. of cor. S. 89° 55' E. on true line.	
11.00	Tudie Willow, 8 lks., flows N.	
40.00	Set post and made mound of stone for $\frac{1}{4}$ sec. corner.	
62.00	Leave valley.	
80.16	To corner. Land, hilly. Soil, good, 2nd rate. Grass, good.	-175
	North on random between secs. 1 and 2.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.	
80.18	Intersected N. boundary, 10 lks. E. of cor. S. 00° 4' E. on true line.	
40.18	Set basalt stone for $\frac{1}{4}$ S. corner.	
80.18	To corner. Land, hilly. Soil, good, 2nd rate. Grass, good.	
	May 5, 1871	
	Survey of Subdivisions of T. 1 N., R. 33 E. Surveyed by Zenas F. Moody under contract No. 164. Dated October 4, 1871.	
40.00	North between secs. 33 and 34. Set post and made mound of earth for $\frac{1}{4}$ sec. corner.	
73.50	Foot of hill.	-600
80.00	Set stone, 30x18x7, for cor. to secs. 33, 34, 27 and 28.	