

Base Line of T. 1 N., R. 33 E.

Chains	<p>Good bunch grass.</p> <p>Scattering pine in canyon.</p> <p style="text-align: right;">June 8, 1887.</p>	
	<p>Thence S.89°51'W. on true line, S. bdy. sec. 35.</p> <p style="text-align: right;">Var. 28°East.</p> <p>Descend.</p>	
13.25	Gulch, course S.	-750
	Ascend.	
30.00	Brow of hill.	+150
40.00	Set basalt stone, 14x12x10 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ S on N. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
41.00	Gulch, course S.	-150
50.00	Summit of hill.	+300
62.60	Gulch, course S.	-300
75.00	Summit of ridge.	+300
80.00	Set post, 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 34 and 35, T. 1 N., R. 33 E. marked S C T 1 N R 33 E. on N. and S 35 on E. and S 34 on W. faces and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
	Land, mountainous and rough. 80 chs.	
	Soil, 1st and 2nd rate. Good grass.	
	<p>Thence S.89°51'W. on true line, S. bdy. sec. 34, T. 1 N., R. 33 E.</p> <p style="text-align: right;">Var. $19\frac{1}{2}$°East.</p>	
2.25	Ravine, course S.	-100
11.00	Summit of hill.	+150
18.50	Gulch, course S.	-150
28.00	Summit, ridge S.	+200
40.00	Set basalt stone, 12x10x10 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound	