

Base Line of T. 1 N., R. 33 E.

Chains 80.00	<p>ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Thence along high Table land.</p> <p>Set basalt stone, 15x7x6 ins., 10 ins. in the ground for cor. to secs. 31 and 32 marked S C with 5 notches on E. and 1 notch on W. edges. Dug pits, 18x18x12 ins., N. E. and W. of stake, $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p> <p>Land, high rolling, 40 chs. mountainous, except last $\frac{1}{2}$ mile which is level.</p> <p>Soil, good.</p> <p style="text-align: right;">June 9, 1887.</p>	
27.00 39.20 40.00 42.50 76.60 78.50	<p>Thence S. $89^{\circ}51'$ W. on true line S. bdy. sec. 31.</p> <p style="text-align: center;">Var. $18^{\circ}10'$ East.</p> <p>Trail bears NE. and SW.</p> <p>Trail bears NE. and SW.</p> <p>Set basalt stone, 10x8x8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Ravine, course N.</p> <p>Trail, bears NW.</p> <p>Cor. to Tps. 1 North, Rgs. 32 and 33 East.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate. Grass, fair.</p>	-100
	<p style="text-align: center;">General Description</p> <p>This line is across high and rough mountains and hill with intervening canyons running S. and S. W. into McKay Creek. On S. and W. slopes the soil is very rocky while on N. and E. slopes it is generally rich, black loam. Grass good. No timber.</p>	