

Subdivisions of T. 1 N., R. 33 E.
 Surveyed by Currin and Noland under special contract.
 Dated May 4, 1887.

Chains		
	Commencing at cor. to secs. 35 and 36, T. 1 N., R. 33 E.	
	on the Base Line I run	
	North between secs. 35 and 36.	
	Var. 28° East.	
	Descend steep mountain side.	
37.00	Canyon, E.	-800
40.00	Set basalt stone, 20x10x6 ins., 15 ins. in the ground for $\frac{1}{2}$ sec. cor. marked $\frac{1}{4}$ on W. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
51.60	Gulch, SE.	-200
	Ascend.	
60.00	Summit ridge, East.	+400
65.00	Canyon, SE.	-300
	Ascend.	
80.00	Set basalt stone, 18x9x9 ins., 12 ins. in the ground for cor. to secs. 25, 26, 35 and 36, marked with 1 notch on S. and E. edges and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable.	+800
	Land, very rough and steep. 80 chs.	
	No timber.	
	Soil, fair on N. hillsides. Bunch grass good.	
	S. hillsides very rocky.	
	East on random between secs. 25 and 36.	
	Var. 14° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.85	Intersect E. bdy. Township, 21 lks. S. of cor. to secs. 25, 36, 30 and 31. Thence S. 89° 51' W. on true line between secs. 25 and 36.	
	Var. 27° East.	
	Descend steep mountain side..	
30.75	Gulch, N.W.	-400
34.00	Canyon, S.W.	-800
39.93	Set basalt stone, 14x10x6 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face and raised mound of	