

## Subdivisions of T. 1 N., R. 33 E.

Chains 40.05	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
55.00	Descend abruptly.	
74.00	Canyon, N. Ascend steep mountain side.	-800
80.10	Cor. to secs. 23, 24, 25, and 26. Land, E. $\frac{1}{2}$ level, W. $\frac{1}{2}$ mountainous. 40 chs. Soil, good. Bunch grass and sunflower.	
	North between secs. 23 and 24. Var. 23° East. Descend.	
31.00	Dry bed of creek in Canyon, N.W.	-800
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised mound of earth and stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
54.00	Canyon, W. Ascend.	-400
75.00	Summit ridge sloping West.	+500
80.00	Set basalt stone, 20x16x6 ins., 15 ins. in the ground for cor. to secs. 13, 14, 23 and 24 marked with 3 notches on S. and 1 notch on East edges, and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, very rough and mountainous. 80 chs. Good bunch grass. Soil, 2nd rate and rocky.	
	East on random between secs. 13 and 24. Var. 23° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.15	Intersect E. bdy. Township at cor. to secs. 13, 24, 18 and 19. Thence	