

Subdivisions of T. 1 N., R. 33 E.

Chains	S. 27' East on true line between secs. 1 and 2. Var. $21\frac{1}{2}^{\circ}$ East. Descend.	
10.80	Dry bed of creek or Tudie Willows.	-400
13.80	Dry bed of branch, N.W. Ascend gradually slope.	
19.20	Set basalt stone, 16x10x8 ins., 12 ins. in the ground for 1/16 sec. cor. marked 1/16 on W. face. Dug pits, 18x18 x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
39.20	Set basalt stone, 10x10x8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
53.00	Top of ridge, N.W.	+500
59.20	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for 1/16 sec. cor. and marked 1/16 on W. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
65.80	Gulch, W.	-100
73.30	Top of ridge, W.	+600
79.20	Cor. to secs. 1, 2, 11 and 12. Land, rolling and high mountainous. 79.20 chs. Soil, good on N. hillsides. Grass fair.	
	From cor. to sec. 34 and 35 on S. bdy. of Tp. I run North between secs. 34 and 35. Var. $19\frac{1}{2}^{\circ}$ East.	
25.00	Summit ridge, E. and W.	
40.00	Set basalt stone, 12x12x12 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on West face and dug pits, 18x18x 12 ins., N. and S. of cor. $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
47.05	Gulch, W.	-600
67.25	Summit ridge W.	
80.00	Set basalt stone, 12x8x5 ins., 8 ins. in the ground for cor. to secs. 26, 27, 34 and 35, marked with 1 notch	