

Subdivisions of T. 1 N., R. 33 E.

Chains	<p>on S. and 2 notches on E. edges. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p> <p>Land, rough and mountainous. 80 chs.</p> <p>Soil, 2nd class. Fine grazing land.</p> <p>Good bunch grass.</p>	
	<p>East on random between secs. 26 and 35.</p> <p style="text-align: center;">Var. $19\frac{1}{2}^{\circ}$ East.</p>	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.00	Intersect N. and S. line, 14 lks. N. of cor. to secs. 25, 26, 35 and 36. Thence	
	N. $89^{\circ}54'W.$ on true line between secs. 26 and 35.	
	Var. 14° East.	
2.50	Gulch.	-40
5.00	Summit ridge, S.W.	+1000
19.90	Ravine, S.	-100
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
41.00	Ravine, S.	-100
62.00	Summit ridge.	+300
	Descend.	
70.00	Canyon.	-100
80.00	Cor. to secs. 26, 27, 34 and 35.	
	Land, very rough and mountainous. 80 chs.	
	Soil, 3rd rate and rocky. Some bunch grass.	
	<p>North between secs. 26 and 27.</p> <p style="text-align: center;">Var. $19\frac{1}{2}^{\circ}$ East.</p>	
9.50	Dry gulch, N.W.	-100
11.00	Summit ridge, W.	+100
14.25	Gulch, West.	-80
19.50	Summit ridge, W.	+100
23.25	Gulch, W.	-150
32.50	Summit hill.	+300