

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 22
35.00	Draw, course N.W.
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
	Thence I run
	West on true line in sec. 22.
	Var. 21°45' East.
15.00	Summit, course N.
19.97	To the ¼ sec. corner between secs. 21 and 22. Land, rolling. Soil, 1st rate. Good grass.
	Sec. 28
	From the corner to secs. 27, 28, 33 and 34, which is a basalt stone, 14x14x14 ins., 8 ins. in the ground marked with 1 notch on S. and 3 notches on E. edges and mound of stone over it.
	Thence I run
	N.89°40'W. on true line between secs. 28 and 33.
	Var. 20° East.
10.00	A dry creek bed winding to West and recross below.
19.92	A rock in place projecting 10x6x4 ft. above ground, which I mark 1/16 on N. face and a cross (+) at exact corner point and raised a stone mound over it. Pits impracticable.
39.85	To the ¼ sec. corner, which is a basalt stone, 18x7x7 ins., 12 ins. in the ground, marked ¼ on N. face. Pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and mound of earth over it.
51.00	Large spring runs N.W.
59.78	Set basalt stone, 12x8x6 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and