

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 29
80.00	<p>To the 1/16 sec. corner between secs. 29 and 30. Land, mostly level. Very little grass. Soil, ashy.</p>
79.88	<p>From the $\frac{1}{4}$ sec. corner between secs. 29 and 30. I run N.89°55'E. on random line in the center through sec. 29. Var. 20°E. Setting temporary corners at 20, 40 and 60 chains, and at Intersect the N. and S. line, 15 lks. N. of $\frac{1}{4}$ sec. corner between secs. 28 and 29. Thence I run N.89°59'W. on true line through the center of sec. 29. Var. same.</p>
19.97	<p>Set basalt stone, 11x9x7 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5$\frac{1}{2}$ ft. dist., and raised a mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>
30.00	<p>Trail, course N. and S.</p>
39.94	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5$\frac{1}{2}$ ft. dist., and raised a mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>
51.40	<p>Spring hollow and stream, 2 lks. wide, course N.W.</p>
59.91	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5$\frac{1}{2}$ ft. dist., and raised a mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>
79.88	<p>To the $\frac{1}{4}$ sec. corner between secs. 29 and 30. Land, mostly level. Very little grass. Soil, ashy.</p>