

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 30
37.50	Draw, course N.W.
38.30	Set basalt stone, 11x8x6 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
58.30	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner, marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
78.30	To the $\frac{1}{4}$ sec. corner between secs. 29 and 30. Land, mostly level. Soil, 2nd rate. Very little vegetation.
	June 21, 1889.
	From the $\frac{1}{16}$ sec. corner, 20 chs. N. of $\frac{1}{4}$ sec. corner between secs. 29 and 30.
	I run
	West on random line through the N. $\frac{1}{2}$ of sec. 30.
	Var. $20^{\circ}30'E$.
	Setting temporary corner at 20, 40 and 60 chs., and at
78.25	Intersect the West bdy. of Tp., 6 lks. S. of $\frac{1}{16}$ sec. cor. in W. bdy. of sec. 30
	Thence I run
	S. $89^{\circ}57'E$. on true line through the N. $\frac{1}{2}$ of sec. 30.
	Var. $20^{\circ}E$.
18.25	Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
38.25	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner, marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.