

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 31
	for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
38.25	Set a basalt stone, 12x8x6 ins., 6 ins. in the ground, for 1/16 sec. cor., marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
51.25	Gulch, course N.W.
58.25	Set a basalt stone, 11x8x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
60.25	Road or trail, course N.W.
78.25	To the 1/16 sec. corner between secs. 31 and 32. Land, level. Soil, 2nd rate. Very little vegetation.
	Sec. 32
	From the corner to secs. 31 and 32 on South bdy. of Township.
	I run
	N.89°51'E. on true line on the South bdy. of sec. 32.
	Var. 18°10'E.
20.00	Set basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised a mound of stone over it. Pits impracticable.
40.00	To the ¼ sec. corner, which is a basalt stone, 16x9x7 ins., 10 ins. in the ground, for ¼ sec. cor. marked ¼ and S C on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and mound of earth over it.
	Land, level.
	Soil, 1st rate.
	Good grass.